



Kia Rio - ABS / ESP control lamp lights up: error code C1606

Data sheet	
Manufacturer	Kia
Vehicle model	Rio
Engine	All models with front camera
Year of manufacture	2018 - 2021
Symptoms	ABS / ESP control lamp lights up
Error code	C1606

Important safety note

ABS / ESP control lamp is on + error code C1606

On the vehicle mentioned above, it is possible that the ABS/ESP control lamp suddenly lights up. Often the error code C1606 (ECU/software error) is then stored in the control unit.

A possible cause is "a software weakness" in the control unit of the front camera.

In order to rule out any other causes, all system-relevant electrical and mechanical components, including the power supply, should be checked before any software update is performed.

A software update can be carried out, for example, via Hella-Gutmann macsRemote Services or by using a pass-through-capable diagnostic device from the mega macs series. Furthermore,

registered access to the vehicle manufacturer's online portal is required. If the appropriate equipment is not available, please contact an authorised specialist workshop.

** ATTENTION - HIGH VOLTAGE**

Please note that this kind of work may only be carried out by an authorised specialist workshop and by appropriately qualified personnel. The repair, maintenance and safety instructions of the vehicle manufacturer are to be strictly observed!



Reprinting, distribution, reproduction, exploitation in any form or disclosure of the contents of this document, even in part, is prohibited without our express, written approval; indication of the document source is also required. The schematic illustrations, pictures and descriptions serve only for the purposes of explanation and representation of the instructions and cannot be used as a basis for installation or assembly work. All rights reserved.