



BMW G31 520d - malfunctioning of instrument cluster

Data sheet	
Manufacturer	BMW
Vehicle model	G31
Engine	520d
Year of manufacture	From 2007
Symptoms	Instrument cluster malfunctioning

Important safety note

Incorrect display on the instrument cluster

On the above-mentioned vehicle model, the display on the instrument cluster may sometimes be offset. This fault occurs after the vehicle has been stationary for a longer period of time and can be rectified for a while again after switching the ignition off/on. This defect may recur at irregular intervals.

If the above-mentioned defect should occur, it may be related to a software error in the instrument cluster. A firmware update of the instrument cluster electronics can help here. In such a case, the software version has to be checked and also updated if necessary. A software update can be carried out, for example, via Hella-Gutmann macsRemote Services or by using a pass-through-capable diagnostic device from the mega macs series. Furthermore, registered access to the vehicle manufacturer's online portal is required.

If the appropriate equipment is not available, please contact an authorised specialist workshop.



IMPORTANT

Please always observe in such cases the maintenance and repair notes provided by the vehicle manufacturer.



Reprinting, distribution, reproduction, exploitation in any form or disclosure of the contents of this document, even in part, is prohibited without our express, written approval; indication of the document source is also required. The schematic illustrations, pictures and descriptions serve only for the purposes of explanation and representation of the instructions and cannot be used as a basis for installation or assembly work. All rights reserved.